



1 PLUMBING FLOOR PLAN (EAST)  
SCALE 1/8" = 1'-0"

**GENERAL NOTES:**

1. REFER TO SHEET P3.01 FOR PLUMBING LEGEND AND GENERAL NOTES.
2. DO NOT INSTALL PIPING AT LOCATIONS THAT WILL INTERFERE WITH SERVICE ACCESSIBILITY TO EQUIPMENT.
3. REFER TO ARCHITECTURAL DRAWINGS FOR DIMENSIONED PLANS, TYPE AND LOCATION OF RATED WALLS AND FLOORS.
4. ALL PIPING ON THIS SHEET IS SHOWN AS ABOVE SLAB UNLESS NOTED OTHERWISE.
5. THIS DRAWING IS SCHEDULE IN NATURE AND IS NOT INTENDED TO SHOW STRUCTURAL OR OTHER BUILDING ELEMENTS REQUIRE ROUTINGS AND LOCATIONS SHOWN WHERE INTERFERENCES WITH COMPONENTS OF OTHER TRADE'S WORK ENGINEER'S APPROVAL PRIOR TO INSTALLATION. NO ADDITIONAL COST SHALL BE GRANTED FOR THESE CHANGES.
6. REFER TO EQUIPMENT MANUFACTURER'S INSTALLATION INSTRUCTIONS FOR ALL AS REQUIRED.
7. VERIFY EXACT LOCATION OF EQUIPMENT PRIOR TO INSTALLATION OF FLOOR BRANS ON FLOOR BRANS.
8. PLUMBING CONTRACTOR TO FIELD VERIFY ALL ELEVATIONS, STRUCTURAL AND CIVIL CONDITIONS PRIOR TO BEGINNING WORK.
9. NOT ALL KEYED NOTES ON THIS SHEET MAY CORRESPOND TO THIS SHEET.

**KEYED NOTES:**

- 1 2" VENT UP FROM BELOW.
- 2 2" WASTE DOWN TO BELOW, 2" VENT UP TO ABOVE.
- 3 4" WASTE DOWN TO BELOW WITH FIGURE 5 FITTING OR APPROVED EQUAL AND CAP ON TOP.
- 4 4" VENT THRU ROOF.
- 5 2" VENT THRU ROOF.
- 6 4" WASTE DOWN TO BELOW. PROVIDE CAP ON TOP OF SANITARY TEE.
- 7 3" DCV BALL VALVE AT 12" ABOVE FINISHED GRADE. PROVIDE UNION AND HOSE BIB WITH VACUUM BREAKER DIRECTLY ABOVE BALL VALVE.
- 8 1/2" DCV DOWN TO WAS3 SHUT-OFF VALVE LOCATED 12" ABOVE FINISHED GRADE.
- 9 2" WASTE DOWN, 2" VENT UP, 1/2" DCV & DHW DOWN.
- 10 2" DCV DOWN.
- 11 2" WASTE DOWN, 2" VENT UP, 1/2" DCV DOWN.
- 12 1/2" DCV AND 1/2" DHW DOWN.
- 13 1 1/4" DCV DOWN.
- 14 2" WASTE DOWN, 2" VENT UP, 1/2" DCV & DHW DOWN.
- 15 1" DCV DOWN.
- 16 PROVIDE DEDICATE SHUT-OFF VALVE BELOW SINK CABINET FOR ICE MAKER. ROUTE 1/4" COPPER TUBING TO ICE MAKER AND MAKE FINAL CONNECTIONS.
- 17 3" VENT UP TO ABOVE.
- 18 3" WASTE UP FROM BELOW TO 3" WOOD. 2" VENT UP FROM TOP OFF 3" TEE.
- 19 1/2" DHW DOWN.
- 20 PROVIDE 3 GPM FLOW CONTROL VALVE ASSEMBLY DIRECTLY ABOVE CEILING IN DHWR LINE. REFER TO GENERAL NOTE 16 P3.01.
- 21 3/4" DCV AND 3/4" DHW DOWN.
- 22 2" WASTE DOWN, 2" VENT UP & 1/2" DCV DOWN.
- 23 1/2" DHW DOWN.

PICT\_51.jpg

6221 Southwest Blvd.  
Fort Worth, Texas 76132  
Tel: 817.231.8100  
Fax: 817.231.8142

DOCUMENT STATUS:	DATE:	APPROVED BY:
01-MASTER PLANNING (MP)	11 NOV 2005	MARK STAFFORD
02-PRELIMINARY DESIGN (PDE)	23 APR 2006	MARK STAFFORD
03-PRICING DOCUMENTS (GMP)	-	- PENDING -
04-CITY REVIEW (CD)	9 JUNE 2008	
05-FOR CONSTRUCTION (CA)		

**INTEGRITY PLUMBING, LLC**  
12018 REATA  
RICHMOND, TEXAS 77469  
PH. 713-828-9028  
TEXAS MPL 26067

STATE OF TEXAS  
MASTER PLUMBER #26067  
MATTHEW G. REYHONS

**Baytown Second Baptist Church**  
**Worship and Education Facilities**  
6227 North Main St., Baytown, Harris County, Tx 77521

**P3.01**  
CLB No. 6362

**PLUMBING FLOOR PLAN**  
**EDUCATION BUILDING (EAST)**  
DRAWN BY: JDH  
CHECKED BY: MR